


Isolation Valve Replacement at Service Connections CB-12 & CB-16

Engineering & Operations Committee Item 8-2 September 10, 2018

Current Action

- Appropriate \$2.78 M
- Award \$866,600 construction to J. F. Shea Construction to replace service connection valves on Rialto Pipeline

Location Map



Background – Valve Replacement



- Valves isolate member agencies' & MWD's systems
- Original construction 1980s
- Valves leak
- Repairs would require shutdown of much of the Rialto Pipeline

Background – Valve Replacement






Old valve type

New valve type

Background – Elect. Improvements

- Current configuration prone to theft
- Requires new electrical ductbank & conduits



&O Committee September 10, 2018

Contractor Scope

- Excavation
- Remove & replace valves during shutdown
- Replace platforms
- Construct new electrical duct bank, panels, & wiring
- Backfill & site restoration

Metropolitan Scope

- Metropolitan force construction
 - Fabricate long-lead items
 - Procure control equipment
 - Shutdown, dewater, test, & fill
 - Configure SCADA system
 - Support activities
 - Construction inspection
 - Contract admin., PM & envir. monitoring
 - Submittals review & record drwgs.
 - Outreach

Bid Results

Specifications No. 1892

Bids received: July 26, 2018

No. of bidders: 3

Low bidder: J. F. Shea Construction Inc.

Low bid: \$866,600

Higher bids: \$934,117 & \$1,050,000

Engineer's estimate: \$809,000

SBE participation: 10%

Requested Funds

Contract	\$866,600
Labor	
Metropolitan force const.	727,000
Construction inspection	247,000
Submittals review & record drwgs.	179,000
Contract admin., R/W, & PM	152,000
Professional services	70,000
Materials	185,000
Remaining budget	353,400

Total

\$ 2,780,000

Total const. cost - \$2,389,600

Schedule





Construction



Board Action



Completion

Board Options

- Option #1
 - Adopt CEQA determination that the proposed action is categorically exempt
 - Appropriate \$2.78 M
 - Award \$866,600 contract to J.F. Shea Construction Inc.

- Option #2
 - Do not proceed with the project at this time

Staff Recommendation

Option #1

